# 2015 Basin Advisory Group Meetings

Harry LaBonde Jr, P.E.

Director

Wyoming Water Development Office

## **Topics**

- Governor's Water Strategy
- Weather Modification Pilot Program

## Governor's Water Strategy

- Started with the Governor's Energy Strategy 2013
  - Objective 9D Wyoming State Water Strategy and Management Plan
- Public Listening Sessions
  - Started in the Fall of 2013
  - 9 Sessions in total
  - Comments were tabulated into 59 potential action items
  - Summary listening session held on June 4, 2014
- Governor's Office in Consultation with Water Agencies
  - Selecting priorities for Governor's consideration

#### Governor's Water Strategy

- Release Date for the Governor's Water Strategy
  - January 2015
- Contents
  - Water Development
  - Water Management
  - Water Conservation and Protection
  - Watershed Restoration
- Water Development
  - Build more storage
    - Ten in Ten Build 10 new reservoirs in the next 10 years
    - WY currently has 16 storage projects in planning, valued at \$473 million
  - Pursue Fontenelle Reservoir riprap project
    - Increase active storage from 260KAF to 345KAF


#### Governor's Water Strategy

- Water Development
  - Glendo Reservoir
    - Re-purpose a portion of the 275KAF now allocated to flood storage
- Water Management
  - Credible Climate, Weather and Stream Flow Data
  - Uniform Hydrographers Operations Manual
  - Groundwater Analysis and Control Area Management Framework
- Water Conservation and Protection
  - Collaborative Planning and Authorization Processes
  - Water Quality Data Integrity Initiative
- Water and Watershed Restoration
  - River Restoration
  - Collaborative Fish Passage Restoration

# Questions

#### Weather Modification Pilot Program

- Goal was to evaluate winter orographic cloud seeding
- Randomized Scientific Study
  - Time Frame: 2008 2014
  - Location: Medicine Bow and Sierra Madre Mountains
  - WMI, Inc. provided all seeding equipment and operational personnel
  - NCAR provided scientific analyses
  - 154 Cases
  - 36 Cases disqualified for quality control issues with precipitation gauges
  - 118 Cases used in the primary statistical analysis



#### Weather Modification Pilot Program

- Results 118 Cases
  - 3% increase in precipitation
  - 28% probability that the results occurred by chance
- Unintended Downwind Effects
  - Modeling studies indicated that 18 cases resulted in downwind precipitation in the Medicine Bow Mountains (control range)
  - 100 Cases Remained
    - Precipitation results increased from 3% to 9%
- Generator Hours (8 generators at 4 hours each = 32 hours max.)
  - Eliminate cases with less than 27 generator hours (38 cases)
  - 62 Cases Remained
    - Precipitation increased from 3% to 17%

- Wind River Mountains
  - 10 Generators used in the Pilot Program
  - First Season of Operations
    - Start Date: November15, 2014
    - End Date: April 30, 2015
    - Total Cost: \$911,393
    - WY share (25% plus management): \$240,000
    - Water users share: 75% (\$684,000)
  - Second Season
    - Total Cost: \$640,000
    - WY share (25% plus management): \$170,000
    - Water users share: 75%

- Wind River Mountains Funding Partners (2014 2015 Season)
  - Central Arizona Project
  - Colorado Water Board of California Six-Agency Committee
  - Southern Nevada Water Authority
  - Arizona Dept. of Water Resources
  - Utah Division of Water Resources
  - US Bureau of Reclamation

#### Big Horn Mountains

- Feasibility Study
- Start Date: July 1, 2015
- Completion Date: July 1, 2016
- Budget: \$300,000

#### Laramie Range Mountains

- Feasibility Study
- Start Date: July 1, 2015
- Completion Date: July 1, 2016
- Budget: \$300,000

- Medicine Bow and Sierra Madre Mountains
  - Design and Permitting
  - Start Date: July 1, 2015
  - Completion Date: December 31, 2016
  - Budget: \$300,000
  - Unknown: Forest Service NEPA process
- All Three New Operational Programs Require:
  - Public Outreach
  - Seek funding commitments for in-basin water users

# Questions